

Upon arrival, the team will take note of any safety information, displays or notices and adhere to the rules of the site at all times.

The driver will ensure that whilst the vehicle is on a designated carriageway or road surface, the rules of that specific highway are abided by at all times.

Should the vehicle be required to travel on any un-designated areas, such as verges or footways, the vehicle will travel at a maximum of 10 miles per hour with the hazard lights flashing at all times. In these specific areas and/or other highly populated areas, the use of a bank's person is recommended but not compulsory.

The area will then be inspected for suitability, at which time, the area the inflatable will cover, will have any large stones or sharp objects removed and disposed of in a sensible & safe manner. The area will then be checked for any height restrictions or for any obstructions. I.e. cables, trees, lights and low ceilings.

The inflatable will then be laid out & unfolded into place. A ground sheet may be used at this point, where necessary. The cables will be laid out and connected to electric or petrol blower or a generator as agreed, prior to our arrival.

The inflation device will then be checked, connected and switched on ensuring all vents are unobstructed, bent or twisted. The remaining vents on the inflatable will then be secured and fastened.

The unit will now be inflated, ensuring that no one is on or near the inflatable.

Then the various anchor points are pegged in place using 12mm x 300mm steel anchor steaks at various points. Not all anchor points require fixing, the fixing of anchor points is dependent on elements such as location, usage, wind speed etc. This will be determined onsite.

When erecting on hard surface, weights/bolts or sand bags may be used and dependent on the circumstances a guide rope may be required. This guide rope may be tied to any fixed object i.e. Fence posts, trees, cars & solid structures.

Hard standing, we can use a drill and bolt the inflatable down safely into the concrete. It will leave a small hole for each bolt. We take no responsibility for any damage at the time or at a later date through drilling a hole for the bolts. Tie offs and weights can be used if we see photos in advance and agree it's safe to do so.

It is imperative that guests or other persons involved in the event do not encroach on the set up area unless specifically requested to do so.

All equipment to be erected as per manufacturers and health and safety guidelines, under no circumstances can this be compromised in any way, regardless of aesthetics or the discretion of the venue and/or organisers.

Where necessary, the hirer should cordon areas off using barrier fencing, rope or tape, we advise this to be done for any public events.

Before use, please read our full Safety Guidelines and Operating Instructions, found on our website.

Upon completion of the event, the inflatables must be evacuated, an allocated member of staff will ensure that no participants are left on the item whilst deflation is in progress.

Once deflation had completed, all anchor pegs, cables, blowers or generators will be carefully removed from site and placed back into the collection vehicles.

The inflatable will then be folded & rolled in an acceptable manor and transported to the vehicle, either by sack truck or wheel cart. When dealing with larger items, the collection vehicle may be required to drive to individual items for collection. The vehicle will travel at a maximum of 10 miles per hour with the hazard lights flashing at all times. In these specific areas and/or other highly populated areas, the use of a banks person is recommended but not compulsory, the rules of the site will be observed at all time.

The area will then be checked for debris and other accessories.

The delivery vehicle will then depart the site, the driver will take note of any safety information, displays or notices and adhere to the rules of the

Please see our full terms and conditions of hire.